

 PRODUCT DRAWING	New Release Form 160.81-PW3 (501)
	WIRING DIAGRAM – FIELD CONNECTIONS MAXE™ YR (STYLE A) ROTARY SCREW CHILLER WITH ELECTRO-MECHANICAL STARTER
YORK INTERNATIONAL CORPORATION P.O. Box 1592, York, PA 17405	
CONTRACTOR _____ ORDER NO. _____ YORK CONTRACT NO. _____ YORK ORDER NO. _____	PURCHASER _____ JOB NAME _____ LOCATION _____ ENGINEER _____
<input type="checkbox"/> REFERENCE DATE _____	<input type="checkbox"/> APPROVAL DATE _____
<input type="checkbox"/> CONSTRUCTION DATE _____	

JOB DATA:

CHILLER MODEL NO. YR _____

NO. OF UNITS _____

COMPRESSOR MOTOR _____ VOLTS, 3-PHASE, _____ HZ

NOTES:

1. All field wiring shall be in accordance with the current edition of the National Electrical Code (N.E.C.) as well as all other applicable codes and specifications.
2. Compressor Motor Frame shall be grounded in accordance with the 1999 N.E.C. (paragraph 250-118) for equipment grounding. Where a separate grounding conductor is used, it must be a copper conductor only and sized per the 1999 N.E.C. (Table 250 -122). Per 1999 N.E.C. (Paragraph 250-(f)(11), where multiple parallel conduits are used, each must contain a grounding conductor. Motor Terminal Box is supplied with a 3/8" hex head cap screw and lockwasher (grounding lug not furnished) for grounding.
3. Wiring, electrical conduit, junction boxes, fused disconnect switches (FDS), or circuit breakers, starters (M), push-button stations (PB), manual-off-automatic switch (S), flow switch (FLS), control relays, and control power transformer (CPT) furnished by others unless otherwise specified.
4. Items marked with an "*" are furnished by York International Corporation.
5. Items marked with "**" are available from York International Corporation at additional cost.
6. Motor starter must be furnished in accordance with Form 160.81-PW7.
7. Control power supply 115V – 50/60 Hz, 15 ampere capacity for control center only, should be supplied by a control power transformer (CPT) wired as shown. CPT should be incorporated in starter (2M), see Note 6.
8. Motor power conduit connection location, motor full load amperes (FLA) and type starting per Product Drawing, Form 160.81-PA1. Multiple conduits shall contain an equal number of wires from each phase in each conduit to prevent overheating, per 1999 N.E.C. (Paragraph 300-20(a)). Use copper conductors only; do not use aluminum conductors. Flexible final connections shall be used to provide vibration isolation.
9. Wiring diagram for YORK OptiView Control Center, Form 160.81-PW1. Field wiring modifications per Form 160.81-PW5.
10. Condenser water pump motor starter (3M) holding coil to be furnished for 115V – 50/60 Hz. The power requirements for the total of the condenser water pump starter (3M) and starter (2M) must be a max.

of 2 amps holding and 10 amps inrush. If power requirements exceed this value, furnish coil for line voltage, and control relay with 115V coil.

11. Units shipped knocked down require field connection of harnesses to control panel. These harnesses are furnished by York International Corporation for field assembly and consist of proper lengths of flexible conduit with necessary connectors, and contain the wires properly terminated and marked.
12. Motor leads shown are for star-delta starter (200 to 600 volts). For 3-lead starting arrangements, see diagram on motor data plate. Connect full voltage (run) interlock of compressor-motor starter to terminals 3 and 4.
13. Wire #14 AWG copper for one way distance of less than 175 feet. Wire #12 AWG copper for one way distance of more than 175 feet, but less than 300 feet.
14. Units installed in Canada must have a field supplied CSA approved 30 amp disconnect switch and 15 amp dual element fuse mounted external to control panel for 115 volt control supply.
15. Control circuit wiring for 3M condenser water pump motor starter is shown for cooling only application.
16. Wiring shown for 200 to 600 volt starter (2M) is required only for optional safety devices in starter which will stop compressor (terminals 15 and 53) and for optional safety devices in the starter which will cycle the compressor and/or optional OFF-AUTO switch (terminals 1 and 13). When optional safety devices are installed, remove jumper between 15 and 53. When optional cycling devices are installed, remove jumper between 1 and 13.

For 200 to 600 volt units, a jumper is provided between terminals 15 and 53. See control center wiring diagram, Form 160.81-PW1 and motor starter, Form 160.81-PW7.

17. Model YR compressor-motors are furnished with six (6) motor terminals (200 thru 600 volts). Motor leads are furnished with a crimp-type connector having a clearance hole for a 3/8" bolt. Motor terminal lugs are not furnished.
18. Starter to motor power wiring ampacity shall be calculated as follows:
 - A. Six lead type of starting (star-delta) – minimum circuit ampacity per conductor (one of six):
$$\text{Ampacity} = .721 \times \text{compressor-motor amps}$$
 - B. Three lead type of starting (across-the-line, auto-transformer, primary reactor or primary resistor) – minimum circuit ampacity per conductor (one of three):
$$\text{Ampacity} = 1.25 \times \text{compressor-motor amps}$$

Where 125% factor is per 1999 N.E.C. (Para. 440-32); .721 is 125% factor x 57.7% voltage (only star-delta starter); compressor-motor amps (see Note 8) are FLA.
19. The fused disconnect switch (FDS2), for the compressor-motor starter, minimum ampere rating shall be determined as follows for 200 to 600 volts:
$$\text{Amp rating} = 1.15 (\text{compressor-motor amps} + \text{control power transformer amps})$$

Where 115% factor is per 1999 N.E.C. (Para. 440-12b(2)); compressor-motor amps (see Note 8) are FLA; the control power transformer is furnished with the compressor-motor starter (2M), control power transformer amps are per Note 20.

20. The full load amperes for the 1.5 KVA control power transformer to be used with Notes 19, 21 and 23 are:

3-PHASE VOLTAGE	HZ	CONTROL POWER (CPT) TRANSFORMER (amps)
200 / 208	60	7.5
220 / 230 / 240	60	6.8
380	60	4.0
416	60	3.6
440 / 460 / 480	60	3.4
550 / 575 / 600	60	2.7
220	50	6.8
346	50	4.3
380 / 400 / 415	50	4.0
440	50	3.4

21. Starter line side power wiring ampacity shall be calculated as follows: minimum circuit ampacity:

$$\text{Ampacity} = 1.25 (\text{compressor-motor amps}) + \text{control power transformer amps}$$

Where 125% factor is per 1999 N.E.C. (Para. 440-33); compressor-motor amps (see Note 8) are FLA; if the control power transformer is furnished with the compressor-motor starter (2M), control power transformer amps are per Note 19.

22. Power factor correction capacitors, when utilized, must be sized to meet the N.E.C. and verified through the local York International office. Improperly installed or sized capacitors may result in equipment malfunction or damage.

23. The branch circuit over current protection device(s) for the 200 thru 600 volt starter (2M) must be a time delay type with a maximum rating equal to the standard fuse/breaker rating equal to or below the following amps:

$$\text{Amps} = 2.25 (\text{compressor-motor amps}) + \text{control power transformer amps}$$

Where 2.25 factor is per 1999 N.E.C. [paragraphs 440-22(a) and (b)]; compressor-motor amps (see Note 8) are FLA. If another power supply (FDS1) is used, enter zero; the control power transformer is furnished with the compressor-motor starter (2M), control power transformer amps are per Note 20.

Fusing and fuse size must be coordinated with starter manufacturer.

The use of circuit breakers with open transition starter is NOT recommended; this combination could result in nuisance tripout on starting.

Starter overload relay trip time is shown in on Product Drawing, Form 160.81-PW7.

24. Automatic control of the chilled water pump by the Control Center is shown. Chilled water pump motor starter (5M) holding coil to be furnished for 115V – 50/60 Hz. The power requirements for the water pump starter (5M) must be a maximum of 2 amps inductive at 115VAC. If power requirements exceed this value, furnish coil for line voltage and control relay with 115V coil.

Two chilled water pump operating modes are available via the CHW Pump programming dip switch (SW1, position 8) on the micro board. With the switch in the “OFF” position, the chilled water pump operates for 30 seconds prior to compressor start, during compressor operation, coast-down, and LWT cycling shutdowns. With the switch in the “ON” position, the chilled water pump operates as above plus it operates during MULTI-UNIT and REMOTE/ LOCAL cycling shutdowns.

For manual chilled water pump control, connect a manual start/stop switch as shown in Detail A.

25. Each 115VAC field-connected inductive load, i.e. relay coil, motor starter coil, etc. shall have a transient suppressor wired (by others) in parallel with its coil, physically located at the coil. Spare transient suppressors are factory supplied in a bag attached to the keypad cable clamp in the OptiView Control Center.

26. The Condenser Flow Switch is optional. If not present, a jumper must be installed between TB4-11 and TB4-1.

